

Louisville and Jefferson County Metropolitan Sewer District 700 West Liberty Street Louisville Kentucky 40203-1911 502-540-6000 www.msdlouky.org

August 17, 2012 (Revised September 20, 2012)

Chief, Environmental Enforcement Section Environmental and Natural Resources Division U.S. Department of Justice Post Office Box 7611 Washington DC 20044-7611

Chief, Water Programs Enforcement Branch Water Management Program US EPA Region 4 Atlanta Federal Center 61 Forsyth Street SW Atlanta, GA 30303 Jeff Cummins, Acting Director Division of Enforcement Department of Environmental Protection 300 Fair Oaks Lane Frankfort, KY 40601

Subject: Southwestern Parkway Storage Basin

Minor Project Modification

IOAP Project No. L OR MF 105 M 13 B A 0

DOJ Case No. 90-5-1-1-08254

Attention Chiefs and Director:

MSD is providing advanced notification of a proposed minor project modification to the Southwestern Parkway Storage Basin project (IOAP Project No. L_OR_MF_105_M_13_B_A_0). This modification is part of an overall adaptive management review of the approved 2009 IOAP that will be documented in the proposed 2012 IOAP Modification to be formally submitted in 2013. No action is requested at this time.

2009 IOAP Project Description

The Southwestern Parkway Storage Basin project entailed the construction of 5.08 million gallons (MG) of offline storage coupled with 8.8 MG of in-line storage from two facilities to be constructed within the Western Outfall and the Northwestern Interceptor to a zero overflow per typical year level of control. The project completion date was set at December 31, 2018.

Proposed Project Modification

Due to the re-calibration of the sewer hydraulic model, the project modification includes the construction of 11.07 MG of offline storage along with the 8.8 MG of in-line storage at the two facilities described above with the project deadline remaining at December 31, 2018. The level of control is higher at zero overflows in a typical year based on a revised benefit/cost analysis.



Southwestern Parkway Storage Basin August 17, 2012 (Revised September 20, 2012) Page 2 of 3

These modifications are part of an overall adaptive management review of the approved 2009 IOAP. Additional sewer system monitoring, hydraulic modeling recalibration and enhancements to the physical representation of the sewer system resulted in a redistribution of the flow in individual sewer lines, thus affecting project approach and sizing in some cases. Each proposed change will be justified in detail through minor modification letters. Detailed benefits, costs and program implementation refinements to the overflow abatement program will be documented in proposed 2012 IOAP Modification to be submitted in 2013. No action is requested at this time.

Technical Justification

As part of an internal modeling review and re-calibration, MSD initiated a detailed review of the combined sewer system hydraulic model utilizing new sewer monitoring data. Upon completion of this review, MSD discovered that the Southwestern Parkway Storage Basin was undersized in the previous submittal.

Since the last IOAP submittal, additional flow monitors have been installed in the system and on the overflow structures. Detailed topographic surveys were conducted at many of the CSO structures. The combined sewer system model was updated with the new survey data and re-calibrated based on the data from the additional flow monitors. The flows in the re-calibrated model differed from the original model and required changes to some of the IOAP projects.

Based on the results of the re-calibration, a level of control analysis was conducted on the Southwestern Parkway Storage Basin. The level of control with the basin sized at 11.07 MG is higher at zero overflows in a typical year. Therefore, MSD proposes to change the Southwestern Parkway Storage Basin solution from 5.08 MG to 11.07 MG. This solution also includes the construction of an in-line control structure on the overflow line to create an additional 8.8 MG of in-line storage. These improvements will maintain the same completion date of December 31, 2018, as the original solution.

For your reference, a copy of the original project fact sheet and map from the 2009 IOAP are in Attachment A. New project fact sheets and maps have been provided in Attachment B. Additional documentation on the costs and level of control analysis will be included in the 2012 IOAP Modification.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering such information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

If you have questions or need additional information, please contact Ms. Angela Akridge, Project WIN Program Manager, or myself at (502) 540-6000.

Southwestern Parkway Storage Basin August 17, 2012 (Revised September 20, 2012) Page 3 of 3

Sincerely,

W. Brian Bingham

Regulatory Services Director

cc:

Greg Heitzman

Paula Purifoy

Attachments



Louisville and Jefferson County Metropolitan Sewer District 700 West Liberty Street Louisville Kentucky 40203-1911 502-540-6000 www.msdlouky.org

August 17, 2012 (Revised September 20, 2012)

Chief, Environmental Enforcement Section Environmental and Natural Resources Division U.S. Department of Justice Post Office Box 7611 Washington DC 20044-7611

Chief, Water Programs Enforcement Branch Water Management Program US EPA Region 4 Atlanta Federal Center 61 Forsyth Street SW Atlanta, GA 30303

Division of Enforcement Department of Environmental Protection 300 Fair Oaks Lane Frankfort, KY 40601

Jeff Cummins, Acting Director

Subject: Southwestern Parkway Storage Basin

Minor Project Modification

IOAP Project No. L OR MF 105 M 13 B A 0

DOJ Case No. 90-5-1-1-08254

Attention Chiefs and Director:

MSD is providing advanced notification of a proposed minor project modification to the Southwestern Parkway Storage Basin project (IOAP Project No. L OR MF 105 M 13 B A 0). This modification is part of an overall adaptive management review of the approved 2009 IOAP that will be documented in the proposed 2012 IOAP Modification to be formally submitted in 2013. No action is requested at this time.

2009 IOAP Project Description

The Southwestern Parkway Storage Basin project entailed the construction of 5.08 million gallons (MG) of offline storage coupled with 8.8 MG of in-line storage from two facilities to be constructed within the Western Outfall and the Northwestern Interceptor to an eight zero overflow per typical year level of control. The project completion date was set at December 31, 2018.

Proposed Project Modification

Due to the re-calibration of the sewer hydraulic model, the project modification includes the construction of 11.07 MG of offline storage along with the 8.8 MG of in-line storage at the two facilities described above with the project deadline remaining at December 31, 2018. The level of control is higher at zero overflows in a typical year based on a revised benefit/cost analysis.



Southwestern Parkway Storage Basin August 17, 2012 (Revised September 20, 2012) Page 2 of 3

These modifications are part of an overall adaptive management review of the approved 2009 IOAP. Additional sewer system monitoring, hydraulic modeling recalibration and enhancements to the physical representation of the sewer system resulted in a redistribution of the flow in individual sewer lines, thus affecting project approach and sizing in some cases. Each proposed change will be justified in detail through minor modification letters. Detailed benefits, costs and program implementation refinements to the overflow abatement program will be documented in proposed 2012 IOAP Modification to be submitted in 2013. No action is requested at this time.

Technical Justification

As part of an internal modeling review and re-calibration, MSD initiated a detailed review of the combined sewer system hydraulic model utilizing new sewer monitoring data. Upon completion of this review, MSD discovered that the Southwestern Parkway Storage Basin was undersized in the previous submittal.

Since the last IOAP submittal, additional flow monitors have been installed in the system and on the overflow structures. Detailed topographic surveys were conducted at many of the CSO structures. The combined sewer system model was updated with the new survey data and re-calibrated based on the data from the additional flow monitors. The flows in the re-calibrated model differed from the original model and required changes to some of the IOAP projects.

Based on the results of the re-calibration, a level of control analysis was conducted on the Southwestern Parkway Storage Basin. The level of control with the basin sized at 11.07 MG is higher at zero overflows in a typical year. Therefore, MSD proposes to change the Southwestern Parkway Storage Basin solution from 5.08 MG to 11.07 MG. This solution also includes the construction of an in-line control structure on the overflow line to create an additional 8.878.8 MG of in-line storage. These improvements will maintain the same completion date of December 31, 2018, as the original solution.

For your reference, a copy of the original project fact sheet and map from the 2009 IOAP are in Attachment A. New project fact sheets and maps have been provided in Attachment B. Additional documentation on the costs and level of control analysis will be included in the 2012 IOAP Modification.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering such information, the information submitted is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

If you have questions or need additional information, please contact Ms. Angela Akridge, Project WIN Program Manager, or myself at (502) 540-6000.

Southwestern Parkway Storage Basin August 17, 2012 (Revised September 20, 2012) Page 3 of 3

Sincerely,

W. Brian Bingham Regulatory Services Director

cc:

Greg Heitzman

Paula Purifoy

Attachments



ATTACHMENT A



CSO LTCP Project Fact Sheet



LTCP Project Number:

L_OR_MF_105_M_13_B_A_0

Project Name:

Southwestern Parkway Storage Basin

Project Type:

RTC with Storage

Receiving Stream:

Ohio River

Project Description:

This project includes a 5.08 MG underground covered concrete basin for CSO104, 105, and 189 and ILS in the WO and the NWI for a total of 8.8 MG using adjustable gates to reduced overflows to zero overflows per year.

Design Parameters / Assumptions: Available CSS storage capacity is based on June, 2001 BPR RTC Study. Flow Control assumes inflatable dams are available at the time of construction. Down-sized storage basin design with Flow Control assumptions are same as Off-line Storage technology.

Surrounding Area Land Use: Project is located within Shawnee Park and approximately 300' West of CSO189.

Apparent Utilities

No major utilities conflict

Description:

ivo major atmacs commet

Capital Projects:

2013~Real Time Control @ Western Outfall (SOR1); 2012~Solids & Floatables CSO104; 2013~RTC - Western

Interceptor - Awaiting Start

Advanced Site Restoration:

The area of the proposed tank is park property. Current and previous public use or development proposals for these areas have identified potential environmental mitigations. The project budget includes a site restoration

allowance.

Estimated Capital Cost

(2008):

\$17,620,000

Capital Cost / Gallon

Overflow Removed:

\$0.13

Weighted Benefit / Cost

28.75

Ratio (Capital Cost):

CSO Number	<u>CSO Name</u>	CSO Area (Acres)	2008 AAOV (MG / Yr)	# of Overflows / Yr	Post LTCP AAOV (MG/Yr)	Post LTCP # Overflows / Year
CSO104	Southwest Parkway Sewer @ Broadway	62.04	0.20	5	0	0
CSO105	Western Outfall @ Broadway	1,881.20	21.43	19	0	0
CSO189	Northwestern Sanitary Diversion	1,148.65	175.79	37	0	0

NOTE: CSO hydraulic statistics are predicted based on InfoWorks model results.




CSO LTCP Project Fact Sheet



LTCP Project Number:

L_OR_MF_105_M_13_B_A_0







ATTACHMENT B



CSO Project Fact Sheet 2012 IOAP Project Modification



Project Name:

Southwestern Parkway Storage Basin

Project Type:

In-Line & Off-Line Storage

Rec Stream:

Ohio River

Project Description:

This project includes a 11.07 MG underground covered concrete basin for CSO104, 105, and 189 and in-line storage in the WO and the NWI for an an additional 8.8 MG using adjustable gates to reduced overflows to zero

overflows per typical year.

Design Assumption:

Available CSS storage capacity is based on June, 2001 BPR RTC Study. Model Run with RTC Coded in confirms

available storage. Flow Control assumes inflatable dams are available at the time of construction.

Capital Cost:

\$33,069,000

Capital Benefit/Cost:

22.14

Present Worth Benefit Cost:

24.06

cso	CSO Name	Existing N	1ay 2012	Baseline May 2012 ²	
		Avg. Annual Overflow Volume	Avg. Annual Frequency	Avg. Annual Overflow Volume	Avg. Annual Frequency
CSO104	SW PKWY SEWER @ BROADWAY	3.90	16	3.90	16
CSO105	WESTERN OUTFALL @ BROADWAY	59.69	30	59.67	30
CSO189	NORTHWESTERN SAN DIV	51.19	28	43.98	28

^{1.} Existing May 2012 conditions reflect existing system operating conditions as of that date.

^{2.} Baseline May 2012 assumes all SSDP projects are complete and critical combined sewer facilities (e.g. Morris Forman WQTC Southwestern Pump Station, Starkey Pump Station) are operating at optimal, sustainable levels.

